William Donald Schaefer Governor

Jacqueline H. Rogers Secretary, DHCD

# INDIVIDUAL PROPERTY/DISTRICT MARYLAND HISTORICAL TRUST INTERNAL NR-ELIGIBILITY REVIEW FORM

TRUST		W 12
Property/District Name: George	W. Helton Farm	Survey Number: M-13-18
Project: 2222 Ridge Rd, Hon MD 27 from MD 355 Site visit by MHT Staff: no	HOMEY Co.	_ Agency: _SHA
Site visit by MHT Staff: no	yes Name	Date
Eligibility recommended	Eligibility not recommend	ded X
Criteria:AB _XCD		BC_D_E_F_GNone
Justification for decision: (Use con	ntinuation sheet if necess	sary and attach map)
Information Si	ubmitted with the	project indicate that for individuos listers. outy for lested. This
the property does nor	+ meet Criteria go	or individual asters.
This farmstead lacks	- Sufficient integ	demonstrated by
moswerely deterior	ted Condition 15	demonstrated by
photos and descri	ptronin project	fele.

Documentation on the property/district is presented	din: Inventory Form - 13-18
Prepared by:  Reviewer, Office of Preservation Services	Beth Hannold  8/30/91  Date
NR program concurrence:	not applicable  30 Ava 91  Date

Survey	No.	M-13-18

# YLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA - HISTORIC CONTEXT

I.	Geographic Region:	
	Western Shore	all Eastern Shore counties, and Cecil) Anne Arundel, Calvert, Charles,
	Piedmont (	Prince George's and St. Mary's) Baltimore City, Baltimore, Carroll, Frederick, Harford, Howard, Montgomery)
	Western Maryland (	Allegany, Garrett and Washington)
II.	Chronological/Developmental Per	riods:
	Paleo-Indian Early Archaic Middle Archaic Late Archaic Early Woodland Middle Woodland Late Woodland/Archaic Contact and Settlement Rural Agrarian Intensification Agricultural-Industrial Transit Industrial/Urban Dominance Modern Period Unknown Period ( prehistori	A.D. 1930-Present
III.	Prehistoric Period Themes:	IV. Historic Period Themes:
	Subsistence Settlement  Political Demographic Religion Technology Environmental Adaption	Agriculture  X Architecture, Landscape Architecture, and Community Planning Economic (Commercial and Industrial) Government/Law Military Religion Social/Educational/Cultural Transportation
v. F	Resource Type:	
	Category: Bulder	res.
	Historic Environment: Mi	iral:
	Historic Function(s) and Use(s	): farmstead
0		
	Known Design Source:	

### CAPSULE SUMMARY

SITE NAME: Hilton Farm

SITE NUMBER: #13/18

APPROXIMATE BUILDING DATE: c. 1904

LOCATION: 22222 Ridge Road, Germantown, Maryland 20874

The Hilton Farmhouse is a large 2 1/2 story, four-bay clapboarded late-Victorian frame structure with a side-gabled roof covered with raised-seamed metal; it rests on a stone foundation and the windows are one/one double sash. Window and door surrounds are plain. There are a number of outbuildings on the site, the most important of which is an early 20th century metal-roofed bank barn covered with vertical plank siding.

#### SITE INFORMATION

M: 13-18

Site Name: George W. Hilton Farm

Site Number: 13-18

County Tax Account Number: 23147

## Name and Address of Property Owner:

Kingstead Manor Joint Venture 7979 Old Georgetown Road Bethesda, MD 20814

#### Master Plan Recommendation:

## <u>Historic Preservation Ordinance Criteria</u>

- (1) Historical and cultural significance. The historic resource:
- X a. Has character, interest or value as part of the development, heritage or cultural characteristics of the county, state or nation;
  - b. Is the site of a significant historic event;
- Z c. Is identified with a person or group of persons who influenced society;
- d. Exemplifies the cultural, economic, social, political or historic heritage of the county and its communities.
- (2) Architectural and design significance. The historic resource:
- <u>X</u> a. Embodies the distinctive characteristics of a type, period, or method of construction;
- b. Represents the work of a master;
- \_\_\_\_ c. Possesses high artistic values;
- d. Represents a significant and distinguishable entity whose components may lack individual distinction; or
- e. Represents an established and familiar visual feature of the neighborhood, community or county due to its singular physical characteristic or landscape.

## Environmental Setting Recommendation:

The environmental setting should be approximately rectangular in shape and bounded by:

Ridge Road on the east;

the row of trees and shrubs behind the outbuildings on the west; the top of the ridge behind the outbuildings to the north; and to the row of trees and the fence approximately 150-200 yards from the house on the south.

The setting would include all of the outbuildings as well as the driveway from Ridge Road to the house.

George W. Hilton Farmhouse (13-18)

## Structural Analysis and Estimate of Costs

prepared by

Hank Handler
Oak Grove Designs
19501 Georgia Avenue
Brookeville, Maryland 20833
(301) 774-0485

## Analysis of structural problems:

The structural condition of the Hilton farmhouse is remarkably good for having stood open and vacant for a long time. Its sound condition can be attributed to the standing-seam tin roof which is for the most part intact. There are, however, a few areas of decay due to failures of the existing roof system. On the southwest face of the house a roofing problem has resulted in water running down the wall on the inside of the house. This condition has existed for quite some time as the signs of decay are easily visible from the exterior of the house.

## Costs to correct structural problems:

Repair of the damage to the southwest wall is likely to involve rebuilding at least half of this side from the foundation to the roof. The rebuilding of the wall would include replacing all structural elements—sills, studs, headers and perhaps joist ends and some roof framing—as well as replacing nonstructural elements, such as siding, fascia, soffit and cornice detailing, and windows and window trim. The costs to correct this structural problem, including these nonstructural elements would be approximately \$20,000.

Except for the southwest wall, the structure of the Hilton farmhouse is sound and there does not appear to be any termite damage.

#### Costs to repair and stabilize the exterior:

Nonstructural exterior areas where complete rebuilding is necessary are the two purches and the three chimneys. The cost to rebuild the porches would be about \$17,000 each; the chimneys would cost about \$4,000 each. The tin roof and gutters, as well as, the wood shingles on the pedimented gable ends, need to be replaced at a total cost of \$28,000.

The windows need to be either replaced or repaired. Most of the sashes are there and if they were repaired, the exterior and interior trim would not need to be replaced. The cost to repair, reglaze and weatherstrip the windows would be about \$25,000. If the windows were replaced, the initial expense would be less, however, the need to replace both exterior and interior trim would add considerably to that cost.

Finally, the cost of repairing and replacing the exterior doors, including those for the basement, would be about \$6,000; scraping and repainting the exterior facade, about \$25,000. The total costs involved in repairing, weatherizing, and stabilizing the exterior structure, including, porches, chimneys, roofing systems, windows, doors, and exterior painting would be approximately \$130,000.

#### Costs to renovate the interior:

order to make the Hilton farmhouse habitable as a single-family residence, the interior must be completely renovated. The kitchen and all the bathrooms would need to be redone at a cost of roughly \$75,000. All mechanical systems, heating, electrical, and plumbing, would have to be replaced for approximately \$50,000. A concrete floor, new stairs, and the removal of an asbestos-covered boiler in the basement would cost \$10,000.

The cost to repair or replace the interior trim, doors and millwork and to sand the floors would be about \$35,000; rebuilding the fireplaces, insulating, plastering and painting the interior would cost \$50,000. The total costs involved in renovating the interior of the Hilton farmhouse comes to \$220,000.

## INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME				
HISTORIC	George W. Hi	lton Farm		
AND/OR COMMON		-		
2 LOCATION	N .			
STREET & NUMBER	22222 Ridge	Road		
CITY, TOWN	Germantown	MONTY OF	CONGRESSIONAL DISTR	RICT
STATE		VICINITY OF	COUNTY	V 17
CLASSIFIC		0 7 =	Montgome	I V
CATEGORY	OWNERSHIP	STATUS	PREC	ENT USE
DISTRICT _XBUILDING(S) STRUCTURE	PUBLIC X_PRIVATE BOTH	OCCUPIED  XUNOCCUPIED  WORK IN PROGRESS	XAGRICULTURE  —COMMERCIAL  —EDUCATIONAL	_MUSEUM _PARA _PRIVATE RESIDENT
S:TE OBJECT	PUBLIC ACQUISITION  _IN PROCESS	ACCESSIBLE  _YES. RESTRICTED	ENTERTAINMENTGOVERNMENT	RELIGIOUS SCIENTIFIC
	BEING CONSIDERED	YES: UNRESTRICTED X_NO	INDUSTRIAL MILITARY	TRANSPORTATION
OWNER OF	BEING CONSIDERED			
NAME .		X_NO	MILITARY	07486
NAME King	PROPERTY stead Manor Joint	X <sub>NO</sub> Venture		07486
NAME King	PROPERTY stead Manor Joint Old Geogetown Roa	X <sub>NO</sub> Venture	_MHEITARY Telephone #:(30	1) 972-3262
NAME King STREET & NUMBER 7979 CITY, TOWN Bethe	FPROPERTY stead Manor Joint Old Geogetown Roa	X_NO  Venture  ad  VICINITY OF	Telephone #: (30	1) 972-3262
STREET & NUMBER 7979 CITY TOWN Bethe LOCATION	SPROPERTY  stead Manor Joint  Old Geogetown Roa esda  OF LEGAL DESCR  Montgomery Co	X_NO  Venture  ad  VICINITY OF	Telephone #:(30  STATE (30  Maryland	1) 972-3262
STREET & NUMBER 7979 CITY TOWN Bethe	SPROPERTY  stead Manor Joint  Old Geogetown Roa esda  OF LEGAL DESCR  Montgomery Co	X NO  Venture  ad  VICINITY OF  RIPTION	Telephone #:(30  STATE (30  Maryland	1) 972-3262
STREET & NUMBER 7979 CITY, TOWN Bethe LOCATION COURTHOUSE RESISTRY OF DEEDS, E	S PROPERTY  stead Manor Joint  Old Geogetown Rose esda  OF LEGAL DESCR  Montgomery Co	X NO  Venture  ad  VICINITY OF  RIPTION	Telephone #:(30  STATE AND Maryland  Liber #: 8053 Folio #: 194	1) 972-3262
STREET & NUMBER 7979 CITY TOWN Bethe LOCATION COURTHOUSE RESISTRY OF DEEDS, E STREET & NUMBER CITY TOWN	SPROPERTY  stead Manor Joint  Old Geogetown Roa esda  OF LEGAL DESCR  Montgomery Co	X.NO  Venture  ad  VICINITY OF  RIPTION  Dunty Courthouse	Telephone #:(30  STATE 4.30  Maryland  Liber #: 8053 Folio #: 194	1) 972-3262
STREET & NUMBER 7979 CITY, TOWN Bethol LOCATION COURTHOUSE PESISTRY OF DEEDS, E STREET & NUMBER CITY, TOWN REPRESEN	S PROPERTY  stead Manor Joint  Old Geogetown Rose esda  OF LEGAL DESCR  Montgomery Co	X.NO  Venture  ad  VICINITY OF  RIPTION  Dunty Courthouse	Telephone #:(30  STATE 4.30  Maryland  Liber #: 8053 Folio #: 194  STATE Maryland	1) 972-3262
STREET & NUMBER 7979 CITY, TOWN Bethol LOCATION COURTHOUSE PESISTRY OF DEEDS, E STREET & NUMBER CITY, TOWN REPRESEN	SPROPERTY stead Manor Joint Old Geogetown Roa esda OF LEGAL DESCR Montgomery Co	Venture  ad  Vicinity of  RIPTION  Dunty Courthouse  ING SURVEYS  ational Atlas of	Telephone #:(30  STATE (30  Maryland  Liber #: 8053 Folio #: 194  STATE  Maryland  Historic Sites	1) 972-3262
STREET & NUMBER 7979 CITY. TOWN Bethe LOCATION COURTHOUSE RESISTRY OF DEEDS, E STREET & NUMBER CITY. TOWN  REPRESENT WITLE MONTO	SPROPERTY  stead Manor Joint  Old Geogetown Roa esda  OF LEGAL DESCR  Montgomery Co  Rockville  FATION IN EXIST  gomery County Loca	Venture  ad  Vicinity of  RIPTION  Dunty Courthouse  ING SURVEYS  ational Atlas of	Telephone #:(30  STATE 4.30  Maryland  Liber #: 8053 Folio #: 194  STATE Maryland	1) 972-3262
STREET & NUMBER 7979 CITY, TOWN Bethe LOCATION COURTHOUSE REGISTRY OF DEEDS, E'STREET & NUMBER CITY, TOWN  REPRESENT TITLE MONTO DATE 1976 DEPOSITORY FOR SURVEY RECORDS M. CITY, TOWN	SPROPERTY stead Manor Joint Old Geogetown Roa esda OF LEGAL DESCR Montgomery Co	Venture  ad  Vicinity of  RIPTION  Dunty Courthouse  ING SURVEYS  ational Atlas of	Telephone #:(30  STATE (30  Maryland  Liber #: 8053 Folio #: 194  STATE  Maryland  Historic Sites	1) 972-3262

## 7 DESCRIPTION

CONDITION

CHECK ONE

CHECK ONE

\_\_EXCELLENT

X DETERIORATED

\_\_UNALTERED

X\_ORIGINAL SITE

\_\_GOOD

\_\_RUINS

\_MOVED DATE\_\_\_

## DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Hilton farmhouse is a large 2½ story, four-bay clapboarded late-Victorian frame structure with a side-gabled roof covered with raised-seamed metal; it rests on a stone foundation and the windows are one/one double-hung sash. Window and door surrounds are plain.

The symmetrical main block, which faces north, has a one-story, shed-roof screened porch which covers the full width of the facade; it rests on brick piers with latticework infill. Originally supported by classical columns, most of the columns are now missing. A centered second-story gable features a shuttered window and scalloped shingles, the same shingles decorate all gable ends. There is an interior chimney at the west end of the roof ridge.

The main facade has two entrances, one in the east bay to the dining room and the other in the west bay to the kitchen

At the south elevation there is a 2½ story, two-bay, gable-roof wing extending to the rear from the southeast corner of the main block. The wing has an outside chimney with a corbelled cap, double windows at the gable end, and an entrance in the westernmost bay. There is a shingled overhang at the second story A one-story, hipped-roof, enclosed porch partially fills in the ell where the main block and the wing meet, at the southwest corner of the house; entrance to the porch is on the west elevation.

The asymmetrical east facade, which faces Ridge Road, features a two-story, semi-hexagonal projecting bay at the northwest corner; there are scalloped shingles and a Palladian window in the gable which caps the bay. Two one-story projecting bays have been added to the east facade, one on either side of the entrance. They are enclosed by six/six double-hung windows. One bay is attached to the southernmost side of the two-story bay and the other is at the southeast corner of the facade. A metal-covered shed roof extends across the entranceway and the two one-story bays, creating another porch.

The entrance on the east facade leads to a central stairhall; the parlor is to the left and the dining room to the right. A second, more narrow stairway to the second floor is located in the kitchen at the rear of the dining room. There are four bedrooms and a bath on the second floor.

(continued)

Interior doors have bullseye corner blocks and architrave surrounds and there are several simple wooden mantels.

There are a number of outbuildings on the site, the most important of which is an early twentieth century metal-roofed bank barn covered with vertical plank siding and resting on a stone foundation; its windows are outlined with paint and there are one-story additions at both gable ends.

The county's remaining barns are a significant part of its cultural heritage because they illustrate the important role which agriculture played in the county's growth and the factors which influenced agricultural development. The bank barn and the dairy barn represent two distinct (but overlapping) phases in that development:

"For nearly 200 years, the barn was the most obvious structure in the Montgomery County landscape. County was overwhelmingly rural in 1900, and, as late as 1950, 67% of its land area was still farmland...The typical late 19th century barn was a large bank barn... built into a hill or bank, so that the stabling area for horse, cows, mules, pigs, and other animals was on on the lower level and opened directly to the outdoors; yet the enormous hayloft above could be entered on the opposite side of the barn also at ground level or up a slight ramp...Barns built well before 1900 were sheathed with a vertical board-and-batten siding, and were ventilated by air entering doors and windows and rising to exit through wood louvered windows high in the walls of the hayloft or up through wood cupolas on the roof ridge. By 1900, barn builders were eliminating the battens and louvers and were allowing air to enter through spaces between the vertical siding...Prior to the 1920s, Montgomery County barns were topped with gable roofs covered with wood shingles. By the 1930s sheet metal was being applied over or in place of the shingles on most barns..."(1)

The dairy barn on the property illustrates the influences which began to change the nature of the dairy industry in Montgomery County in the 1920s, as more stringent health regulations forced county dairy farmers to replace the all-purpose bank barn with more modern dairy facilities:

"A major transition in barn design occurred during the 1920s...a result of several factors: the rise of dairy farming as a major industry, the stricter regulations imposed on dairy barns, the introduction of a new type of roof structure, the increased use of concrete block...By 1922, sanitation standards had become more important and ...By 1930...many farmers were constructing examples of the new, sanitary barn...Devoted solely to the milking of cows, they have concrete milking floors with haylofts above. They are not bank barns, but are all on one level.

The walls of the barn are built of molded concrete blocks rusticated, {in some cases} rock-faced in other examples...Attention was paid to aesthetics by providing blocks of contrasting color for window and door surrounds and quoins at corners...The interiors...were made as sanitary as possible through the use of a concrete floor with manure trough, plastered walls and ceilings finished with tight fitting boards...gambrel roofs shelter unobstructed haylofts...steel cupolas (provided ventilation)...The 'home-built wood cupola' was spurned...Concrete blocks were preferred to wood because they could provide smooth, clean interior walls. They also were readily available by the 1930s and, unlike poured concrete, they required a minimum of skill to use. Thus throughout the 1930s and for decades afterwards, concrete blocks were used for cattle barns."(2)

The dairying complex on the Hilton farm includes the clapboard-and-concrete-block, metal-roof dairy barn (probably erected about 1923), a tile-covered, hipped-roof equipment building, and twin tile-covered silos, one of which has dormer windows at its peak.

Other outbuildings date from the early-mid twentieth century and include a double corn crib and machine storage shed with cat-slide roof, also covered with vertical plank siding; a shed-roof, vertical-sided hen house; and a number of smaller outbuildings (built with vertical plank siding or concrete block, with shed or gable roofs) used for equipment storage or livestock.

The Hilton farmhouse is in a deteriorated condition, as are some of the outbuildings.

#### Footnotes

- 1. A. Rebeck, "Twentieth Century Barns in Montgomery County", pps.2-5.
- Ibid.

PERIOD	Al	REAS OF SIGNIFICANCE CH	IECK AND JUSTIFY BELOW	
PREHISTORIC	ARCHEULOGY-PREHISTORIC	COMMUNITY PLANNING	_LANDSCAPE ARCHITECTURE	RELIGION
_1400-1499	ARCHEOLOGY-HISTORIC	CONSERVATION	_LAW	SCIENCE
_1500-1599	XAGRICULTURE	ECONOMICS	LITERATURE	SCULPTURE
1600-1699	ARCHITECTURE	EDUCATION	MILITARY	SOCIAL HUMANITARIAN
_1700-1799	ART	ENGINEERING	MUSIC	THEATER
1800-1899	COMMERCE	$X_{\sf EXPLORATION/SETTLEMENT}$	PHILOSOPHY	TRANSPORTATION
X <sub>1</sub> 900-	COMMUNICATIONS	INDUSTRY	POLITICS/GOVERNMENT	OTHER SPECIFY
		INVENTION		
SPECIFIC DAT	ES c.1904	BUILDER/ARCH	HITECT Edward Mauric	ce Beall (builder) nknown)

STATEMENT OF SIGNIFICANCE

The Hilton Farm is historically significant because it is an intact early twentieth century farm complex which is representative of the county significant age of farming, from the mid-nineteenth to the mid-twentieth century (1). In addition, several of its owners have been members of prominent county families, or have, individually, gained prominence in the community. Architecturally, the Hilton farmhouse is significant as a late-Victorian vernacular dwelling which, because of its substantial size, reflects a degree of prosperity which sets it apart from more modest early farmhouses. It is also a prominent visual feature in the neighborhood and one of a rapidly-dwindling number of such early structures in the area.

The Hilton farmhouse is located on part of approximately 250 acres which Charles Riggs Purdum acquired in 1837 from Basil Waters. (2) Purdum (who was the great-grandfather of the Kings who owned the property in the 1970s and 1980s) died in 1864, leaving the property to his widow, Margaret. The Martenet & Bond map for 1865 shows Margaret Purdum's dwelling.

In 1868, after Margaret Purdum's remarriage, the property was ordered sold under a court order, with the proceeds to be divided among Purdum's eight children. Thomas Anderson was appointed trustee for the sale of Purdum's property, described as "200-250 acres, with a comfortable dwelling, a barn, and two tobacco houses...worth \$20 an acre " The property was divided into three lots and lot #1, containing 124 acres (part of two tracts known as "The Resurvey of Locust Levels" and "The Addition to Erocke Grove") was sold to George W. and Frances C. Hilton for \$35.50 an acre, one quarter acre was reserved for a graveyard. The dower lot, which was reserved for Purdum's widow, contained 36½ acres and a one-bay, two-story, gable-roof dwelling. (4)

(continued)

An improvement of \$372 appears on the tax records for Hilton's property in 1876, indicating that he may have erected a house by then; the 1878 Hopkins Atlas also shows him as owning property in the area. $^{(5)}(6)$ 

George Hilton, who probably erected the original house on the site, was a prosperous businessman and farmer who also served in the state legislature and held other public offices. Born in Laytonsville in 1823, Hilton began his career as a school teacher; in 1847 he was appointed to his first public post, as "Deputy Sheriff and Collector". Hilton served two terms in the legislature, from 1869 to 1875, and, in 1877, was appointed by the Governor to the Board of Control and Review, which set tax assessments.

Hilton "engaged in merchandising" in Damascus from 1852-1858. In 1859 he purchased property in Clarksburg, moved there, and opened a new business. The 1865 Martenet and Bond Map shows George W. Hilton as the owner of a dwelling and store on Clarksburg's Main Street. As T.H.S. Boyd comments in his history of Montgomery County (written in 1879):

"By energy and enterprise, combined with strict business integrity, (Hilton) succeeded in establishing a large and profitable business (in Clarksburg), which he conducted until 1872, when he turned his attention to agricultural pursuits. Having purchased four tracts of land adjacent to the village of Clarksburg he set about renovating and improving them......Mr. Hilton finds ample opportunity for the display of his spirit of enterprise in the improvement and beautifying of his lands and tenements, having erected several handsome dwellings in Clarksburg......"(7)

The original farmhouse on the site may have been one of the "handsome dwellings" referred to by Boyd.

In 1880, Hilton sold all of lot #1 containing 124 acres to Edward L. Beall, a member of another prominent family in the area; Edward L. Beall died intestate about 1903. The 124 acre property was then sold to Edward L. Beall's son, Edward M. Beall, and, after Edward M. Beall's death in 1939, it was conveyed to his son, William M. Beall. In 1961, William M. Beall sold the property to Leslie King, who conveyed it to his nine children in 1972. It remained in the possession of the King family (prominent early settlers in the area), until the mid-1980s, when it was sold for development. (8)

According to a family member, it was Edward M. Beall who erected the existing house in the early 1900s, after demolishing the earlier structure on the site; he also moved the family graves to the Upper Seneca Baptist Church graveyard in Cedar Grove. (9) Tax records for the period corroborate this, showing an increase in "improvements" from \$950 in 1903 to \$1575 in 1904, indicating that the existing farmhouse was probably built between 1903 and 1904. Substantial increases in the value of improvements are listed in 1910, 1912 and 1923, when it may have been

enlarged. Also in 1923, a cow barn, a silo, and dairy building are listed for the first time. The value of the dwelling (according to the tax records) remained the same from 1923-1940, indicating that all the additions were probably in place by 1923. (10) According to members of the King family, the appearance of the house has not changed since 1940.

The farmhouse has been vacant sine the 1950s, and dairying operations were suspended in the 1970s, but the property continues to be operated as a farm, as it has for over a century.

The history of the King family's settlement in the area dates from approximately 1798, when John Duckett King moved from southern Maryland to Damascus, settling in an area now known as Kings Valley. A tobacco grower and father of 14 children, John King was the founder of a family which has been actively engaged in farming in Montgomery County for at least five generations; King family dairying operations, in particular, have attracted national and international attention. As the obituary for Leslie King (who owned and operated the Hilton farm from 1961-1972 although he lived on a neighboring farm) noted:

".......(his) achievements in dairying were so significant that he was held by his fellow dairy farmers and breeders in the same high esteem and respect duly accorded a king in any land."(11)

The Hilton Farm has, essentially, remained in the same family since the mid-1800s, since the Purdums, Hiltons, Bealls and Kings were all related by marriage or birth. Early settlers in the area, they all contributed significantly to the growth and development of the county, particularly in the years when farming and dairying were its most important industries.

#### Footnotes

- 1. A. Rebeck, "Twentieth Century Barns in Montgomery County", p.7.
- 2. Land Records, Montgomery County, Maryland, BS 8/333.
- 3. 1865 Martenet & Bond Map of Montgomery County, Maryland.
- 4. Judgement Record EBP 1/92, Montgomery County, Maryland
- 5. Tax Records, Second District, 1876, Montgomery County, Maryland
- 6. 1878 Hopkins Atlas.
- 7. T.H.S. Boyd, The History of Montgomery County, Maryland, pps.94 & 95
- 8. Land Records, Montgomery County, Maryland, EBP 5/384, TD 24/321, 735/336, 2814/599, 4452/44
- 9. Interviews with Jane and Douglas King, January 1990.
- 10. Tax Records, Second District, 1903-1940, Montgomery County, Maryland.
- 11. Leslie King obituary, Montgomery County Sentinel, Dec. 4, 1974.

## 9 MAJOR BIBLIOGRAPHICAL REFERENCES

Attached

CONTINUE ON SEPARATE SHEET IF NECESS	ESSARY	NECES:	IF	SHEET	SEPARATE	ON	CONTINUE
--------------------------------------	--------	--------	----	-------	----------	----	----------

## 10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 111.07 acres

VERBAL BOUNDARY DESCRIPTION

Attached

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE

COUNTY

STATE

COUNTY

## 11 FORM PREPARED BY

NAME / TITLE:

Lois Snyderman, Consultant

	Rockville	Maryland	
CITY OR TOWN		STATE	
	51 Monroe Street	(301) 217-3625	
STREET & NUMBER		TELEPHONE	
	Historic Preservation Commission	Feb. 1990	
ORGANIZATION		DATE	

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust

The Shaw House, 21 State Circle

Annapolis, Maryland 21401

(301) 267-1438

- G.M. Hopkins 1878 Atlas of Montgomery County, Maryland, Montgomery County Library, Rockville, Maryland.
- <u>History of Maryland 1812-1880</u>, J. Thomas Scharf, 3 Volumes, Tradition Press, Hatboro, Pennsylvania, 1967.
- Index to Montgomery County Wills, 1777-1941, County Courthouse, Rockville, Maryland.
- Montgomery County Land and Equity Records, County Courthouse, Rockville, Maryland.
- Montgomery County Tax Assessment Records, Second District, Hall of Records, Annapolis, Maryland.
- <u>History of Montgomery County</u>, Maryland, T.H.S. Boyd, Regional Publishing Co., Baltimore, Maryland, 1972.

Interview with Jane King, January 1990.

- Martenet & Bond's Map of Montgomery County, Maryland, 1865.
- A. Rebeck, "Twentieth Century Barns in Montgomery County", files of the Historic Preservation Commission, Rockville, Maryland, undated.

## LSSR 053 FRE 2 C |

#### MCE TREE

Being part of the land recorded in said Liber 4452 at Polio 44.

BESTINGING FOR THE SAME at a point on the 6th or South 55° 30° 00°

West 2046.00 feet line of the above described Parcel One, being located

808.25 feet from the beginning thereof; thence running with part of said

line and with the extension of said line, the following course

- 1) North 55° 30' 00° East 1468.25 feet to a point; thence
- 2) North 08° 30' 00" West 330.00 feet to a point; thence
- 3) North 01° 00' 00" East 1179.75 feet to a point; thence
- 4) North 78° 15' 00" East 1183.98 feet to a point; thence
- 5) South 01° 00' 00" West 293.00 feet to a point; thence
- 6) North 77° 40' 00° West 115.15 feet to a point; thence
- 7) South 01° 00' 00° West 544.50 feet to a point; thence
- 8) South 77° 40' 00° East 367.11 feet to a point; thence
- 9) South 03° 15' 00° East 13.48 feet to a point; thence
- 10) South 00° 51' 06° West 523.46 feet to a point of curvature; thence
- 22.31 feet along the arc of a curve deflecting to the right, having a radius of 2825.25 feet (Chord: Eouth 01° 04' 40" West 22.31 feet) to a point; thence
- 12) North 80° 15' 00° West 213.95 feet to a point; thence
- 13) South 00° 30' 00" Wost 95.00 feet to a point; thence
- 14) South 80° 15' 30° East 211.00 feet to a point; thence
- 15) 909.17 feet along the arc of a curve deflecting to the right, naving a radius of 2825.25 feet (Chord: South 12° 26' 28° Mest 905.26 feet) to a point; thence

PAGE 3 OF 4

DECEMBER 1, 1987

### 1228053729202

- 16) South 21° 39' 36" West 283.52 feet to a point of curvature; thence
- 17) 525.56 feet along the arc of a curve deflecting to the left, haing a radius of 3454.19 feet (Churd: South 17° 18' 04" West 525.05 feet) to a point; thence
- 18) South 22° 15' 00" West 260.46 feet to a point; thence
- 19) North 81° 00' 00" West 1447.88 feet to a paint; thence
- 20) North 42° 30° 00° West 853.88 feet to the point of beginning, containing 112.70 acres, more or less.

DEC. 3 1987

2.1- 22883

23147

sil Taxes on assessments certified to allector of a sees for Montgomery Crist by Advisor have been paid Deniance Montgomery County, Md. The mont is fur fire purpose of permitting rund-tin and is not assurance against to be taxation even fur pure periods, not does in guarantee satisfaction of outstanding tax sales.

\$ 58 057.80 TRANSFER TAX PAID MONTGOMERY COUNTY, MARYLAND

HE AUDIO TRANSTER

590

10000 \$ 286, 638.55

Doyle D. Eng

State Department of Assessments & Taxation for Montgomery County

PAGE 4 OF 4

DECEMBER 1, 1987

## MARYLAND HISTORICAL TRUST

1601595635

# INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

								<del></del>
<b>I</b> NAME								
HISTORIC								
HISTORIC	Geor	ge W. Hilton Fa	arm					
AND/OR COM		<u> </u>		····				
	L.C.	King Farm						
2 LOCA	TION							
-								
STREET & NL		27 (Ridge Roa	a )					
CITY, TOWN	RLE.	27 (Ridge Road	<u>u)</u>			co	NGRESSIONAL DISTRI	СТ
	Clar	ksburg	VI	CINITY OF	(Brink			
STATE						_	unty cgomery	
	Mary					MOIT	gomery	
3 CLASS	SIFICA	ATION					•	
				4			/ 5056	ENTUSE
CATE		OWNERSHIP	•	STATUS			AGRICULTURE	MUSEUM
DISTRICT		PUBLIC		OCCUPIED				PARK
<b>₩</b> BUILDIN	G(S)	Y_PRIVATE		UNOCCUPIE			COMMERCIAL	7
STRUCTI	URE	BOTH		_WORK IN PE	ROGRESS		EDUCATIONAL	¥PRIVATE RESIDENCE
SITE		PUBLIC ACQUISITI	ON	ACCESS	IBLE		ENTERTAINMENT	RELIGIOUS
OBJECT		_IN PROCESS		YES: RESTR	ICTED		GOVERNMENT	SCIENTIFIC
		BEING CONSIDERED		YES: UNRES	TRICTED		_INDUSTRIAL	_TRANSPORTATION
				√NO			MILITARY	OTHER:
NAME		PROPERTY Lie C. King & S	ons		1	Tele	phone #:	
STREET & N								
	King	stead Road						
CITY, TOWN						Мэ	STATE, Z ryland	ip code
		ascus		ICINITY OF		ria	Lyrand	
5 LOCA	TION	OF LEGAL DES	CRI	PTION		Libe	r #:	
COURTHOU	SE					Foli	o #:	
REGISTRY (		Montgomery	Cour	ity Cour			- "	
STREET & N	UMBER			<del></del>				
CITY, TOWN							STATE	
Ciri. 107711		kville					Maryland	
a prop		TATION IN EX	CTI	NG STIR	VEYS			
TLIK!	L JE IV	IAHONINEA		AG DOM				
TITLE								
DATE					FEDERAL	_STATE	COUNTYLOCA	
DEPOSIT <b>OR</b> SURVEY RE	_		-					
CITY, TOWN	1						STATE	

CONDITION

\_EXCELLENT \_GOOD

\_\_DETERIORATED

\_\_GOOD \_\_FAIR \_\_RUINS
\_\_UNEXPOSED

**CHECK ONE** 

\_\_UNALTERED

CHECK ONE

YORIGINAL SITE

MOVED DATE\_\_\_\_

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

PERIOD	AF	REAS OF SIGNIFICANCE CH	ECK AND JUSTIFY BELOW	
PREHISTORIC	ARCHEULUGY-PREHISTORIC	COMMUNITY PLANNING	LANDSCAPE ARCHITECTURE	RELIGION
1400-1499	_ARCHEOLOGY-HISTORIC	CONSERVATION	_LAW	SCIENCE
1500-1599	AGRICULTURE	ECONOMICS	LITERATURE	SCULPTURE
1600-1699	ARCHITECTURE	EDUCATION	MILITARY	SOCIAL HUMANITARIAN
/1700-1799	ART	ENGINEERING	MUSIC	THEATER
<u>√</u> 1800-1899	COMMERCE	_EXPLORATION/SETTLEMENT	PHILOSOPHY	TPANSPORTATION
1900-	COMMUNICATIONS	INDUSTRY	POLITICS, GOVERNMENT	OTHER (SPECIFY)
		INVENTION		
SPECIFIC DAT	ES	BUILDER/ARCI	HITECT	

STATEMENT OF SIGNIFICANCE

This is a Victorian farmhouse, built in several sections. Unable to view close-up. but the two-story frame house may be that shown on the 1878 map as owned by George W. Hilton. Mr. Hilton was a prominent farmer and businessman in Clarksburg during the 19th Century.

Now a working dairy farm owned by the King family, who are nationally recognized dairy farmers.

## MAJOR BIBLIOGRAPHICAL REFERENCES

<u>HISTORY OF MONTGOMERY COUNTY</u>, <u>MD</u>. Boyds, 1879. p.p. 94, 95, 124, 125.


CONTINUE ON SEPARATE SHEET IF NECESSARY


EOGRAPHICAL DATA  ACREAGE OF NOMINATED PROPERTY	
VERBAL BOUNDARY DESCRIPTION	•
99 + A#554	en de la companya de La companya de la co
LIST ALL STATES AND COUNTIES FOR PROPE	RTIES OVERLAPPING STATE OR COUNTY BOUNDARIES
STATE .	COUNTY
STATE	COUNTY
SIAIE	COONIT
	COUNTY
ORM PREPARED BY	
ORM PREPARED BY	r Park Historian
ORM PREPARED BY  Michael F. Dwyer, Senio	r Park Historian
ORM PREPARED BY  AME/TITLE  Michael F. Dwyer, Senio	r Park Historian DATE 3/22/74
ORM PREPARED BY  AME/TITLE  Michael F. Dwyer, Senio  RGANIZATION  M-NCPPC  TREET & NUMBER	r Park Historian  DATE  3/22/74  TELEPHONE
CORM PREPARED BY  AME/TITLE  Michael F. Dwyer, Senio  RGANIZATION  M-NCPPC	r Park Historian  DATE  3/22/74  TELEPHONE  589-1480
FORM PREPARED BY  AME / TITLE  Michael F. Dwyer, Senio  RGANIZATION  M-NCPPC  TREET & NUMBER	r Park Historian  DATE  3/22/74  TELEPHONE

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438





<u>Legend:</u>

\* Historic Parcel

M: <u>13-18</u>: George W. Hilton Farm 22222 Ridge Road

Germantown, Maryland

Scale: 1"=200"

1" = 200'



Hilton Farm SIte HM. 13/16 22222 Ridge Road Gernantown, MD Fast Elevation Lois Snyderman, 12/89



Hilton Farm Sie +41.13/18 22222 Ridge Rd Germantown, MD West Elevation Lois Snyderman, 12/89



Hilton Form Site 41/13/18 22222 Ridge Rd Germantown, MD South Elevation Lois Snyderman, 12/89



Hilton Farm Sie#1.1318 22 222 Ridge Rd Germantown, MD East Elevation Lois Snyderman, 12/89



Hilton Farm Site #M13 18 22222 Ridge Rd Germantown, MD North Elevation Lois Snyderman, 12/89



Hilton Farm Site #M:13/18 22222 Ridge Rd Germantown, MD Outbuilding - East - Worth Bank Barn Lois Snyderman, 1/90



Hilton Farm Site 411. 13 18 22222 Ridge Rd Germantown, MD Outbuilding (SHE)-Bank Barn Lois Snyderman, 12/89



Hilton Farm Sie #13/18 22222 Ridge Rd. Germantown, MD. Outbuildings - Dairy Barn, 51/05 Lois Snyderman, 12/89



Hilton Farm Sie # 13/18 22222 Ridge Road Germantown, MD Outbuildings- (Fast) Corn Crib Machine Storage Lois Snyderman 15/80



Hilton Farm Sie 4113/18 22222 Ridge Road Germantown, MD Outwilding South Elevation Lois Snyderman, 190



Hom Farm Site #M:13/18 22222 Ridge Rd Germantown, MD Outwilling North Elevation Lois Snyderman 12/89



Hilton Farm Site 4m.13/18 22222 Ridge Rd. Germantown, MD Outlouilding - South | East Elevations Lois Snyderman, 12/89



Hilton Farm Sie 41:13/18 22222 Ridge Rd Germantown, MD Outbuilding LOIS Snyderman, 12/89



Hilton Farm Sie # 13/18 22222 Ridge Rd Germantown, MD OUTBUILDING - EAST ELEVATION LOIS SNYD ERMAN, 1/90



Hilton Farm Site #1:13/18 22222 Ridge Rd Germantown, MD Out building - (South) Dairy Equipment Lois Snyderman, 1/90



NAME M. # 13-18 GEORGE W. HILTON FARM (L.C. KING FARM)
LOCATION RTE, 27, CEDAR GROUE, MD.

FACADE LOOKING W
THOTO TAKEN 3/22/74 M. DWYER.